

ACCO NOBO S17E

ACCO NOBO S17E



Brief Introduction

Beta 2.5

The NOBO S17E DLP has 1800 Ansi lumens, a contrast of 2000:1 and an SVGA 800 x 600 resolution. Due to the brightness of 1800 Ansi lumens, a picture width of 369 cm is possible. In room light, the picture should be max. 246 cm wide. The model was built by ACCO in 2007 and is no longer current.

Display Type



1 x 0,55" DDR 12 Grad DLP Chip
SVGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

1800 / 1450 im Eco Mode

582 Lux (bei 203 cm Screen)

Contrast

2000:1 full on/off

2000:1 full on/off

Black Level

0,9000 min. Lumen

0.291 min. Lumen

Offset

Resolution

SVGA 800 x 600

480.000 Pixel

Video Modes

SXGA 1280 x 1024 compressed

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

170W SHP Lamp

Light Life

Articel Nr.: SP.82G01.001

2000 h. 3000 h. in Eco Mode

Operating Costs

30,95% / 0,13 €

Focus

Manual

Zoom

Manual 1,10

Objective

F=2,35-2,47 f=21,83-23,81 mm

Throw Ratio

1,93-2,13:1

Audio

No

Connections

D-sub 15pin in 1 x out

S-Video in

Cinch Video in

RS232C

USB in

Mini Jack in

Ceiling Mounting

Yes

Power


265W / 15W standby

Size WxHxD

230 x 95 x 210 mm (9,1"x3,7"x8,3") 4,59 L/dm³

Operating Noise

33 / 28 dB in Eco Mode



Key: 211 cm

Weight 2,00 kg / 4,41 lbs.
Keystone Vert.: +/-16°
Illumination 85%

Frequenz V-sync: 31,5-68,7 Hz

Foot-Lamberts 54 fL / max. 369 cm screen width
185 cd/m²

Features

- Freeze
- Eco Mode
- Kensington Slot
- sRGB
- Password protection
- Remote control with mouse control
- Digital Zoom
- 5-segment colour wheel.
- De-interlacer with 3:2 2:2 pull down..

Bulb only NLMP4753

Lamp ruby Ruby-LMP4753

Optional Lamp original SP.82G01.001

Compatible lamp LMP-K16490

Status Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n16491>
2007 Discontinued (EOL) // Last update of the data: 2023-08-04



More Details



HCinema
<https://www.projector-database.com/pro/ACCONOBOS17e-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.