

ACTO DX125



ACTO DX125



Brief Introduction

Beta 2.5

The DX125 3D DLP projector from ACTO has 3200 Ansi lumens, a contrast of 2600:1 and an XGA 1024 x 768 resolution. An image width of up to 493 cm is possible. However, the image should be smaller in room light. We recommend max. 329 cm. The model was built by ACTO in 2011 and is no longer current.

Display Type



1 x 0,55" DLP Chip
XGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

Projector 3200

Screen 1067 Lux (bei 200 cm Screen)

Contrast

2600:1 full on/off

Screen 2600:1 full on/off

Black Level

1,2308 min. Lumen

Screen 0,411 min. Lumen

Offset

-

Resolution

XGA 1024 x 768

786.432 Pixel

SXGA 1280 x 1024 compressed

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

3D Compatibility

Frame Sequential (3D Ready)

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Light Source

230W SHP Lamp

Light Life

3000 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,1

Objective

-

Throw Ratio

1,94-2,13:1

Audio

-

Connections

D-sub 15 pin in und out

S-Video in

Cinch Video in

RS232C

USB Typ B

Ceiling Mounting

Yes

Power

280W

Size WxHxD

264 x 78 x 208 mm (10,4"x3,1"x8,2") 4,28 L/dm³

Operating Noise

36dB

Weight

2,50 kg / 5,51 lbs.

Keystone

Vert.: +/-15°

Illumination

85%

Frequenz



H-sync: 15-110 kHz

V-sync: 50-80 Hz

Foot-Lamberts

99 fL / max. 493 cm screen width

339 cd/m²



Features

Status

Data

■ Eco Mode

■ 6-segment colour wheel.

2011 Discontinued (EOL) // Last update of the data: 2023-08-04

More Details



HCinema

<https://www.projector-database.com/pro/actodx125-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.