

ASK Proxima C520



ASK PROXIMA C520



Brief Introduction

Beta 2.5

The ASK Proxima model C520 is an LCD projector with XGA 1024 x 768 resolution and a contrast of 5000:1. The built-in lens shift and keystone correction function provides freedom when setting up. An image width of up to 646 cm is possible as the projector has 5500 Ansi lumens. The projector can create rooms with residual light with a smaller image width, we recommend a maximum of 431 cm. If the image is still too small, the integrated edge blending software can help to project a larger image with additional projectors. The model was built by ASK Proxima in 2014 and is no longer current.

Display Type



3 x 0,63" LCD TFT Panel
XGA 4/3 Liquid Crystal Display

Ansi-Lumen

5500

1833 Lux (bei 200 cm Screen)

Contrast

5000:1 full on/off

5000:1 full on/off

Black Level

1,1000 min. Lumen

0,367 min. Lumen

Lens shift

Vert.: +/-40% Hori.: +/-10%

Resolution

XGA 1024 x 768

786.432 Pixel

Video Modes

UXGA 1600 x 1200 compressed

Pal, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Light Source

280W Lamp

Light Life

3000 h. 4000 h. in eco Mode

Operating Costs

-

Focus

Manual

Zoom

Manual 1,65

Objective

F=1,6-2,08 f=19,36-31,94 mm

Throw Ratio

1,51-2,5:1

Audio

10W

Connections

HDMI in
2 x D-sub 15pin in 1 x out
Cinch Video in
S-Video in
Mini Jack Audio in und out
USB in
RS232C Din 9 pin in
RJ45 in

Ceiling Mounting

Yes

Power


375W

Size WxHxD

385 x 110 x 308 mm (15,2"x4,3"x12,1") 13,04 L/dm³

Operating Noise

36 / 32 dB in Eco Mode



Weight

4,85 kg / 10,69 lbs.

Keystone

Vert.: +/-30°
Hori.: +/-15°

Illumination

80%

Frequenz
H-sync: 15-100 kHz
V-sync: 48-85 Hz

Foot-Lamberts
170 fL / max. 646 cm screen width

582 cd/m²

■ Lens shift Funktion
■ User logo
■ Eco Mode
■ Kensington Slot
■ Edge Blending
■ Lan network compatible.

Status
2014 Discontinued (EOL) // Last update of the data: 2023-08-04

Data
Created: 2014-08-20 14:04:44



More Details



HCinema

<https://www.projector-database.com/pro/askproximac520-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.