

Barco Galaxy

BARCO GALAXY



Brief Introduction

Beta 2.5

The Barco Galaxy DLP projector has 5000 Ansi lumens, a contrast of 800:1 and an SXGA 1280 x 1024 resolution. Including a lens shift function, which provides freedom during installation. Thanks to the brightness of 5000 Ansi lumens, a picture width of 599 cm is possible. The projector can also handle slightly brighter rooms with a smaller image width (we recommend max. 399 cm). The model was built by Barco in 2002 and is no longer current.

Display Type



3 x DLP DMD Chip
SXGA 5/4 Ti Digital Light Processing Chip

Ansi-Lumen

5000

1517 Lux (bei 203 cm Screen)

Contrast

800:1 full on/off

800:1 full on/off

Black Level

6,2500 min. Lumen

1.904 min. Lumen

Lens shift

Vert.: +/-59% Hori.: +/-35,5%

Resolution

SXGA 1280 x 1024

1.310.720 Pixel

Video Modes

NTSC, PAL, SECAM, NTSC 4.43, HDTV

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Wide screen width or rooms with plenty of light (over 200 lumens).

Light Source

1200W Xenon Lamp

Articel Nr.: R9840740 R9840820

Light Life

1000 h.

Operating Costs

-

Focus

Powered

Zoom

Powered

Objective

optional

Throw Ratio

optional

Audio

No

Connections

RS232C

5 x BNC RGBHV

Cinch Video

S-Video

Ceiling Mounting

Yes

Power


1600W

Size WxHxD


529 x 408 x 795 mm (20,8"x16,1"x31,3") 171,59 L/dm³

Operating Noise

50dB



Weight	45,00 kg / 99,21 lbs.
Keystone	-
Illumination	-
Frequenz	-
Foot-Lamberts	141 fL / max. 599 cm screen width 483 cd/m²
Features	■ Lens shift Funktion



Optional Lenses					
Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
R9840910	5-8:1	10.2-16.2 m			Powered
R9840690	2.8-5:1	5.7-10.2 m			Powered
R9840680	2-2.8:1	4.1-5.7 m			Powered
R9840670	1.6-2:1	3.2-4.1 m			Powered
Fix Optional Lenses					
R9840900	0.8:1	1.6 m			No Zoom
R9840770	1.2:1	2.4 m			No Zoom

Status2002 Discontinued (EOL) // Last update of the data: 2023-10-26

Data



More Details



HCinema

<https://www.projector-database.com/pro/barcogalaxy-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.