


Barco ID R600



BARCO ID R600



Brief Introduction

Beta 2.5

The Barco ID R600 BrilliantColor DLP projector has 6000 Ansi lumens, a contrast of 2000:1 new / 1500:1 old and an SXGA+ 1400 x 1050 resolution. The built-in lens shift function provides freedom when setting up. An image width of up to 675 cm is possible, if the image width is smaller (we recommend max. 450 cm), rooms with residual light are also no problem. If the image width is not sufficient, the projector offers integrated edge blending software, with which several projectors can project a large image together. The model was built by Barco in 2005 and is no longer current.

Display Type



1 x 0,95" DC3 DLP Chip
SXGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

6000

2000 Lux (bei 200 cm Screen)

Contrast

2000:1 neu / 1500:1 alt full on/off

2000:1 neu / 1500:1 alt full on/off

Black Level

3,0000 min. Lumen

1,002 min. Lumen

Lens shift

Vert.: +47,5% --15%

SXGA+ 1400 x 1050

Resolution

1.470.000 Pixel

UXGA 1600 x 1200 compressed

Video Modes

PAL, PAL-M, PAL-N, PAL-60, SECAM, NTSC, EDTV HDTV 720p, 1080i,

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Very large screen width and rooms with plenty of light and shaded daylight.

Light Source

2 x 250W UHP Lamp

Articel Nr.: R9841823

Light Life

1500 h. 3000 h. in singel lamp Mode

Operating Costs

-

Focus

Powered

Zoom

Powered

Objective

optional

Throw Ratio

optional

Audio

-

Connections

DVI
5 x RNC RGBHV in
D-sub 15pin in
1 x BNC Video in
S-Video in
Weitere optional

Ceiling Mounting

Yes

Power


650W

Size WxHxD

415 x 195 x 590 mm (16,3"x7,7"x23,2") 47,75 L/dm³

Operating Noise

-



Weight

12,90 kg / 28,44 lbs.

Keystone

-

Illumination

95%

Frequenz H-sync: 15-110 kHz
V-sync: 25-150 Hz

Foot-Lamberts 186 fL / max. 675 cm screen width

637 cd/m²

- Features
- Lens shift Funktion
 - Freeze
 - Gamma correction
 - Edge Blending
 - Picture-in-Picture
 - Password protection
 - BrilliantColor™
 - Remote control with backlight
 - digital zoom
 - Efficient seamless blending

Please note Laut dem Exel Kalkulator stimmen die Shiftwerte im Prospekt nicht.

Optional	Philips bulb only	NLMP17827
	Bulb only Philips	NLMP17828
	Single lamp ruby	Ruby-LMP17827
	Twin lamp original	R9841842 / R9841823
	Single lamp original	R9841822
	Compatible lamp	LMP-K15939
	Air filter compatible	Alternative zu:R9842800

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n15939>

Optional Lenses					
Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
QCLD (1,1-1,3:1)	1.13-1.33:1	2.3-2.7 m	55-15%		Powered
CLD(2,4-4,3:1)	2.37-4.32:1	4.7-8.6 m	55-15%		Powered
CLD(1,6-2,4:1)	1.58-2.39:1	3.2-4.8 m	55-15%		Powered
CLD(1,2-1,6:1)	1.2-1.64:1	2.4-3.3 m	55-15%		Powered
Fix Optional Lenses					
QCLD (0,85:1)	0.89:1	1.8 m	0.0% Fix		No Zoom

Status Data 2005 Discontinued (EOL) // Last update of the data: 2023-08-04

More Details



HCinema

<https://www.projector-database.com/pro/barcoidr600-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.

