


Boxlight ProjectoWrite2/W



Brief Introduction

Beta 2.5

The ProjectoWrite2/W LCD projector from Boxlight has 3000 Ansi lumens, a contrast of 500:1 and an XGA 1024 x 768 resolution. An image width of up to 477 cm is possible as the projector has 3000 Ansi lumens. However, if room light is available, the image should be max. 318 cm wide. The projector is equipped with an integrated whiteboard function for interactive training and presentations. The model was built by Boxlight in 2010 and is no longer current.

Display Type

3 x 0,63" LCD TFT Panel
XGA 4/3 Liquid Crystal Display

Ansi-Lumen

3000 / 1950 im Eco Mode 1000 Lux (bei 200 cm Screen)

Contrast

500:1 full on/off 500:1 full on/off

Black Level

6,0000 min. Lumen 2,012 min. Lumen

Offset

-
XGA 1024 x 768
786.432 Pixel

Resolution

UXGA 1600 x 1200 compressed

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application

Whiteboard | Training and company presentations, as well as product presentations.
Medium screen width or rooms with a little more ambient light, max. 200 lumens.

Light Source

230W UHP Lamp
Articel Nr.: SEATTLEX30N-930

Light Life

2000 h. 3000 h. in Eco Mode

Operating Costs

-

Focus

Manual

Zoom

Manual 1,18

Objective

-

Throw Ratio

1,47-1,73:1

Audio

1 x 8W

Connections

DVI-I in
D-sub 15 pin in und out
S-Video in
Cinch video in
Mini Jack Audio in
USB
RS232C Din 9 pin in
RJ45 in

Ceiling Mounting

Yes

Power

310W

Size WxHxD

325 x 97 x 260 mm (12,8"x3,8"x10,2") 8,2 L/dm³

Operating Noise

33 / 30 dB in Eco Mode

Weight


3,30 kg / 7,28 lbs.

Keystone

Vert.: +/-30°

Illumination

-



Frequenz	H-sync: 31-92 kHz V-sync: 48-120 Hz	
Foot-Lamberts	93 fL / max. 477 cm screen width 319 cd/m²	
Features	■ Freeze ■ User logo ■ Eco Mode ■ Kensington Slot ■ Remote control with laser pointer und mouse control ■ Lan network compatible. ■ Digital zoom ■ Whiteboard function	
Optional	Bulb only NLMP24261 Lamp original SEATTLEX30N-930	
Status Data	Order here: https://www.hcinema.de/lampen/shop-en.php?id=n19720 2010 Discontinued (EOL) // Last update of the data: 2023-08-04	

More Details



HCinema

<https://www.projector-database.com/pro/boxlightprojectowrite2-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.