

LG CX135

LG CX135



Brief Introduction

Beta 2.5

With the CX135, manufacturer LG offers a standard portable DLP projector with XGA 1024 x 768 resolution and a contrast of 2000:1. The projector will be able to illuminate a screen width of 493 cm well. However, if room light is available, the picture width should ideally not exceed 329 cm. The model was built by LG in 2005 and is no longer current.



1 x 0,7" DLP Chip

XGA 4/3 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen

3200

1067 Lux (bei 200 cm Screen)

Contrast

2000:1 full on/off

2000:1 full on/off

Black Level

1,6000 min. Lumen

0,534 min. Lumen

Offset

Resolution

XGA 1024 x 768

786.432 Pixel

SXGA+ 1400 x 1050 compressed

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Medium screen width or rooms with a little more ambient light, max. 200 lumens.

Light Source

300W P-VIP Lamp

Light Life

2000 h. 3000 h. in Eco Mode

Operating Costs

-

Focus

Manual

Zoom

Manual 1,2

Objective

f=23,62-28,26 mm

Throw Ratio

1,66-1,99:1

Audio

2W Mono

Connections

DVI mit HDCP

D-sub 15pin in

Cinch Video in

S-Video in

USB

RS232C

Ceiling Mounting

Yes

Power


-

Size WxHxD

308 x 97 x 241 mm (12,1"x3,8"x9,5") 7,2 L/dm³

Operating Noise

30 dB in Eco Mode



Weight

2,70 kg / 5,95 lbs.

Keystone


Vert.: +/-15°


Illumination

85%

Frequenz

-



Foot-Lamberts	99 fL / max. 493 cm screen width	
Features	339 cd/m²	
Status	■ Eco Mode	
Data	2005 Discontinued (EOL) // Last update of the data: 2023-08-04	

More Details



HCinema

<https://www.projector-database.com/pro/lgcx135-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.