

Liesegang dv 800

LIESEGGANG DV 800

Brief Introduction

Beta 2.5

The Liesegang dv 800 LCD projector has 400 Ansi lumens, a contrast of 100:1 and an SVGA 800 x 600 resolution. A picture width of up to 174 cm is possible as the projector has 400 Ansi lumens. However, if room light is available, the image should be a maximum of 116 cm wide. The model was built by Liesegang in 1996 and is no longer current. It should also be noted that there are unfortunately no more replacement lamps for the projector, neither originals nor replicas.

Display Type

1 x 4,09" LCD TFT Panel
SVGA 4/3 Liquid Crystal Display

Ansi-Lumen

400

133 Lux (200 cm Screen width)

Contrast

100:1 full on/off

100:1 full on/off

Black Level

4,0000 min. Lumen

1,37 min. Lumen

Offset

-

Resolution

SVGA 800 x 600
480.000 Pixel

Video Modes

PAL, NTSC 3,58, NTSC 4,43-System

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Very narrow picture width and rooms with very little light.

Light Source

575W Metalldampf Lamp
Article Nr.: ZU0643 02 2060

Light Life

750 h.

Operating Costs

-

Focus

Manual

Zoom

-

Objective

f=300-335 mm

Throw Ratio

3,61-4,03:1

Audio

2 x 10W

Connections

S-Video in
1 x Video Cinch in
1 x Cinch Stereo in
weitere

Ceiling Mounting

-

Power

800W

Size WxHxD

380 x 270 x 650 mm (15"x10,6"x25,6") 66,69 L/dm³

Operating Noise

-

Weight

17,00 kg / 37,48 lbs.

Keystone

-

Illumination

-

Frequenz

H-sync: 14-80 kHz
V-sync: 40-120 Hz

Foot-Lamberts


12 fL / max. 174 cm screen width
41 cd/m²

Features

-

Screen Mirroring

-



Optional accessories

Lampe Original	ZU0643 02 2060	EOL €
 Luftfilter universal	uni3mm	18,15 €

Status Data 1996 Discontinued (EOL) // Last update of the data: 2026-06-09



HCinema

<https://www.projector-database.com/pro/liesegangdv800-en.html>

More Details

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.