

METAvision CHT 723



With the CHT 723, manufacturer METAvision offers a DLP projector with WXGA 1280 x 768 resolution and a contrast of 3600:1. The integrated lens shift provides freedom when positioning the projector. 287 cm image width, the projector will be able to illuminate well. However, if room light is available, the image width should ideally not exceed 191 cm. The model was built by METAvision in 2006 and is no longer up to date. It should also be noted that there are unfortunately no more replacement lamps for the projector, neither originals nor replicas.

Brief Introduction
Beta 2.5

Display Type

 1 x 0,65" DC2 DLP Chip
WXGA 15/9 Ti Digital Light Processing Chip

Ansi-Lumen

800 333 Lux (bei 200 cm Screen)

Contrast

3600:1 full on/off 3600:1 full on/off

Black Level

0,2222 min. Lumen 0,093 min. Lumen

Lens shift

Vert.: +65% -50% Hori.: +/-15% manuell

Resolution

WXGA 1280 x 768
983.040 Pixel

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Disc Recognition

DVD | HD Blu-ray (komprimiert) | 3D-Blu-ray | 4K-UHD-Blu-ray

Application

Homecinema | Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

250 / 200W im Eco Mode Lamp

Light Life

Articel Nr.: LMP15995
2000 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,25

Objective

F=2,4-2,5 f=19,1-23,9 mm

Throw Ratio

1,34-1,68:1

Audio

-

Connections

DVI-D mit HDCP
D-sub 15 pin in
2 x YUV in
RS232C

Ceiling Mounting

Yes

Power


370W / 5W standby

Size WxHxD

342 x 144 x 320 mm (13,5"x5,7"x12,6") 15,76 L/dm³

Operating Noise

30 dB in Eco Mode



Weight	6,30 kg / 13,89 lbs.
Keystone	Vert.: +/-15°
Illumination	-
Frequenz	-
Foot-Lamberts	31 fL / max. 287 cm screen width 106 cd/m²
Features	■ Lens shift Funktion manuell ■ Eco Mode ■ De-interlacer with 3:2 2:2 pull down ■ 6 segment colour wheel 6X speed.
Status	2006 Discontinued (EOL) // Last update of the data: 2023-08-04



Data



More Details



HCinema

<https://www.projector-database.com/pro/metavisioncht723-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.