

Mitsubishi XL2E/U



MITSUBISHI XL2E/U



A brief introduction to the Mitsubishi XL2E/U. The LCD projector has an XGA 1024 x 768 resolution and a contrast of 350:1. The built-in ambient light sensor detects the ambient light in the room and automatically optimizes the image. The projector can illuminate a picture width of up to 302 cm thanks to its 1200 Ansi lumens. In ambient light, however, the picture width should ideally be less than 201 cm. The model was built by Mitsubishi in 2002 and is no longer current.

Brief Introduction

Beta 2.5

Display Type



3 x 0,7" LCD TFT Panel
XGA 4/3 Liquid Crystal Display

Ansi-Lumen

Projector 1200

Screen 388 Lux (bei 203 cm Screen)

Contrast

350:1 full on/off

Screen 350:1 full on/off

Black Level

Offset 3,4286 min. Lumen

Screen 1.118 min. Lumen

Resolution

XGA 1024 x 768

786.432 Pixel

SXGA 1280 x 1024 compressed

Video Modes

NTSC/NTSC 4.43/PAL (inkl. PAL-M, N)/SECAM/PAL-60/DVD (Komponente)/HDTV (525p, 720p, 1.080i)

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

150W Lamp

Articel Nr.: VLT-XL2LP

Light Life

2500 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,19

Objective

F=1,9-2,2 f=27-32 mm

Throw Ratio

1,8-2,2:1

Audio

1W

Connections

Cinch Video in

S-Video in

Cinch Stereo in

D-Sub 15pin in und out

RS232C (DIN 8-polig),

Ceiling Mounting

Yes

Power

230W

Size WxHxD

237 x 94 x 315 mm (9,3"x3,7"x12,4") 7,02 L/dm³

Operating Noise

34dB

Weight


2,90 kg / 4,41 lbs.

Keystone

Vertical

Illumination

-



Frequenz H-sync: 15,0-69,0 kHz
V-sync: 50-85 Hz
Range max.: 100 MHz

Foot-Lamberts 36 fL / max. 302 cm screen width

123 cd/m²

Features

- Freeze
- Eco Mode
- Kensington Slot
- sRGB
- Gamma correction
- Picture-in-Picture
- Remote control with laser pointer
- Ambient Light Sensor.
- RIS® (Room Illumination Sensor)
- digital zoom
- ColorView
- CineView

Optional	Lamp ruby	Ruby-LMP2406
	Lamp original	VLT-XL2LP
	Compatible lamp	LMP-K15969
	Universal Remote original	Fernb-uni-V3
	Remote control original	939P927010

Status Data

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=d15969>
2002 Discontinued (EOL) // Last update of the data: 2023-08-12

More Details



<https://www.projector-database.com/pro/mitsubishixl2u-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.