

Nec PX602UL /WH/BK

NEC PX602UL /WH/BK



The Nec PX602UL /WH/BK 3D laser DLP projector has 6000 Ansi lumens, a contrast of 10000:1 and a WUXGA 1920 x 1200 resolution. The manufacturer specifies a laser service life of 20000 hours, which is over 13.7 years if enjoyed for four hours a day. The integrated lens shift gives freedom when positioning the projector. 787 cm image width, the projector will be able to illuminate well. The projector can manage rooms with residual light with a smaller image width, we recommend a maximum of 525 cm. If the image is still too small, the integrated edge blending software can help to project a larger image with additional projectors. The model is also compatible with Full HD 1080P and 4K (compressed) as well as 3D, meaning that all Blu-ray formats currently available can be recognized by the projector. The model was built by Nec in 2014 and is no longer current.



1 x 0,67" DLP Chip
WUXGA 16/9 Ti Digital Light Processing Chip

Brief Introduction

Beta 2.5

Display Type

Ansi-Lumen

Contrast

Black Level

Lens shift

Resolution

Video Modes

3D Compatibility

Application

Light Source

Light Life

Operating Costs

Focus

Zoom

Objective

Projector
6000
10000:1 full on/off
0,6000 min. Lumen

Vert.: +/-50% Hori.: +/-15%
WUXGA 1920 x 1200

2.304.000 Pixel
HD4K 4096 x 2160 compressed

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 4K UHD (komprimiert), 3D, EDTV 480p, 576p

Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom
Frame Sequential (3D Ready)

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Very large screen width and rooms with plenty of light and shaded daylight.

Laser Light Source

Article Nr.: 7N901041 / RD-465E

20000 h.


0,00 € Laser



Powered

Powered

optional

Screen
2667 Lux (bei 200 cm Screen)
10000:1 full on/off
0,267 min. Lumen



Throw Ratio	optional	
Audio	Nein	
Connections	HDMI in und out D-sub 15pin in und out 5 x BNC RGBHV in S-Video über BNC in BNC Video in Mini Jack Audio in und out USB Typ A in RS232C Din 9 pin in RJ45 mit HDBaseT in 3D SYNC	16/9 screen width:200 cm Screen:1 Gain
Ceiling Mounting	Yes, is possible.	
Power	530W	
Size WxHxD	484 x 195 x 509 mm (19,1"x7,7"x20")	
Operating Noise	38dB	
Weight	18,50 kg / 40,79 lbs.	
Keystone	Vert.: +/-40° Hori.: +/-40°	
Illumination	-	
Frequenz	-	
Foot-Lamberts	248 fL / max. 787 cm screen width 850 cd/m² ■ Real Full HD 3D ■ Full HD 1080P compatible ■ Direkt Power Off ■ Lens shift Funktion ■ Freeze ■ User logo ■ Eco Mode ■ 360° installable ■ Edge Blending ■ Password protection ■ Remote control with backlight ■ PJLink™ ■ Lan network compatible. ■ Crestron®-Software compatible. ■ Picture-in-picture ■ Picture-and-side-by-side ■ DICOM Simulation;	
Features		
Screen Mirroring	-	

Optional accessories			
	Objektiv Original	100013847 / NP37ZL	3.576,32 €
	Objektiv Original	100013844 / NP34ZL	EOL €
	Objektiv Original	100013847 / NP37ZL	3.576,32 €
	Objektiv Original	100013763 / NP35ZL	2.717,31 €
	Objektiv Original	100013844 / NP34ZL	EOL €
	Fernbedienung Original	7N901041 / RD-465E	101,45 €



Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
NP37ZL	1.53-2.94:1	3.1-5.9 m			Powered
NP35ZL	1.23-1.54:1	2.5-3.1 m	+/-50%	+/-15%	Powered
NP34ZL	0.96-1.23:1	1.9-2.5 m	+/-50%	+/-15%	Powered

Status 2014 Discontinued (EOL) // Last update of the data: 2025-03-03
Created: 2014-11-13 14:05:26

Data



More Details



HCinema

<https://www.projector-database.com/pro/necPX602UL-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.