

Nec NP2200

NEC NP2200



Brief Introduction

Beta 2.5

The NP2200 LCD projector from Nec has 4200 Ansi-Lumen, a contrast of 600:1 and an XGA 1024 x 768 resolution. Including a lens shift and keystone correction function, which provides freedom during installation. Thanks to the brightness of 4200 Ansi lumens, an image width of 564 cm is possible. The projector can also handle slightly brighter rooms with a smaller picture width (we recommend a maximum of 376 cm). The model was built by Nec in 2010 and is no longer current.

Display Type



3 x 0,8" LCD TFT Panel mit MLA
XGA 4/3 Liquid Crystal Display with Micro Lense Array

Ansi-Lumen

Projector 4200

Screen 1400 Lux (bei 200 cm Screen)

Contrast

600:1 full on/off

600:1 full on/off

Black Level

7,0000 min. Lumen

2,345 min. Lumen

Lens shift

Vert.: +50% -0% Hori.: +/-10% manuell

Resolution

XGA 1024 x 768

786.432 Pixel

Video Modes

UXGA 1600 x 1200 compressed

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Wide screen width or rooms with plenty of light (over 200 lumens).

Light Source

300 / 264W NSH Lamp

Light Life

Articel Nr.: NP06LP / 60002234

2000 h. 3000 h. inEco Mode

Operating Costs

-

Focus

Manual

Zoom

Manual 1,33

Objective

F=1,7-2,2 f=24,4-32,5 mm

Throw Ratio


1,52-2,03:1

Audio

2 x 5W Stereo

Connections

DVI-D mit HDCP in
D-sub 15pin in und out
5 x BNC RGBHV in
S-Video in
Cinch Video in
2 x Cinch Stereo in 1 x out
RJ45in



RS232C
USB Typ A
Mini Jack in



Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes
381 / 334W in Eco Mode
399 x 150 x 358 mm (15,7"x5,9"x14,1") 21,43 L/dm³
34 / 30 dB in Eco Mode

Weight
Keystone
Illumination

7,40 kg / 16,31 lbs.
Vert.: +/-30°
-

Frequenz

H-sync: 15-100 kHz
V-sync: 50-120 Hz

Foot-Lamberts

130 fL / max. 564 cm screen width
445 cd/m²


- Direkt Power Off
- Lens shift Funktion manuell
- Freeze
- Blackboard Modus
- Eco Mode
- Kensington Slot
- sRGB
- Gamma correction
- Digital image shift
- Picture-in-Picture
- Password protection
- Remote control with laser pointer
- Control via web browser
- Wi-Fi network compatible.
- Lan network compatible.
- Overscan adjustable
- Auto colour correction,
- remote control with mouse control,
- 3-fold security system,
- 4-fold digital zoom,

Features

Philips bulb only NLMP16859
Lamp ruby Ruby-LMP16859
Lamp incl. air filter original NP06LP / 60002234 / NP06LP+
Compatible lamp LMP-K16859
Remote control original 7N901053 / RD-469E / 7N900881 / RD-443E
Ceiling Mount 100-120 Halterung100

Optional

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n19525>



Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
NP05ZL	4.83-7.34:1	9.7-14.7 m	50%	+/-10%	Manual
NP04ZL	3.05-4.89:1	6.1-9.8 m	50%	+/-10%	Manual
NP03ZL	2.01-3.17:1	4-6.3 m	50%	+/-10%	Manual
NP02ZL	1.22-1.59:1	2.4-3.2 m	50%	+/-10%	Manual

Fix Optional Lenses

NP01FL	0.83:1	1.7 m	0.0% Fix		No Zoom
--------	--------	-------	----------	--	---------

Status 2010 Discontinued (EOL) // Last update of the data: 2023-08-04



Data



More Details

HCinema

<https://www.projector-database.com/pro/necnp2200-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.