

Philips NeoPix Prime

PHILIPS NEOPIX PRIME



The Philips NeoPix Prime model is an LCD LED projector with HDTV 1280 x 720 resolution and a contrast of 3000:1. The manufacturer Philips states a service life of 20000 hours, which converts to over 13.7 years at 4 hours of use. The projector also offers an integrated media player that can be used to play files directly. As Philips specifies the brightness of the projector in lumens, we have calculated an approximate Ansi lumen value in this case. The projector can illuminate a picture width of up to 388 cm well with its 1458 Ansi lumens. In room lighting, however, the picture width should ideally be less than 259 cm. The model recognizes screen mirroring signals, so it is possible to play videos with high resolution and surround sound directly via WLAN from a smartphone, tablet or PC (Android, Windows and iOS). Even 1080P video signals are no problem for the projector. The model was built by Philips in 2019 and is no longer current, but is still one of the very popular projectors.

Brief Introduction Beta 2.5

Display Type

LCD TFT Panel
HDTV 16/9 Liquid Crystal Display

Ansi-Lumen

1458 / 3500 LED Lumen

648 Lux (bei 200 cm Screen)

Contrast

3000:1

3000:1

Black Level Offset

0,4860 min. Lumen

0,216 min. Lumen

Resolution

HDTV 1280 x 720

921.600 Pixel

HDTV 1920 x 1080 compressed

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, EDTV 480p, 576p

Application

Media player formats: .dat/.mpg/.mpeg/.ts/.trp/.tp/.vob/.mp4/.mkv /.avi/.flv/.3gp

Micro-Portabel | Small mobile presentations..

Light Source

LED

Light Life

20000 h.

Operating Costs

0,00 € LED

Focus

Manual

Zoom

No Zoom

Objective

-

Throw Ratio


1,4:1

Audio

2 x 5W

Connections

2x HDMI in
Mini Jack Audio in und out
USB in





Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes
100W
220 x 170 x 90 mm (8,7"x6,7"x3,5") 3,37 L/dm³
-

Weight
Keystone
Illumination
Frequenz

1,20 kg / 2,2 lbs.
-
-
-

Foot-Lamberts

60 fL / max. 388 cm screen width
206 cd/m²

Features

- Full HD 1080P compatible
- Integrated Mediaplayer
- Wi-Fi network compatible.
- Bluetooth

Status

2019 Discontinued (EOL) // Last update of the data: 2024-06-04
Created: 2020-03-06 12:31:18

Data

More Details



HCinema

<https://www.projector-database.com/pro/philipsneopixprime-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.