


Runco VX 44d

RUNCO VX 44D



Brief Introduction

Beta 2.5

A brief introduction to the Runco VX 44d. The stationary DLP projector has an HDTV 1920 x 1080 resolution and a contrast of 2000:1. The built-in lens shift function provides freedom when setting up. The projector can illuminate a screen width of up to 643 cm thanks to its 4000 Ansi lumens. The projector can create rooms with residual light with a smaller image width, we recommend a maximum of 429 cm. Furthermore, the projector can play 1080P without any problems. The model was built by Runco in 2006 and is no longer current. Unfortunately, we can no longer offer a replacement lamp for this model, neither original nor replica.

Display Type

3 x 0,95" DLP Chip
HDTV 16/9 Ti Digital Light Processing Chip

Ansi-Lumen

4000

1778 Lux (bei 200 cm Screen)

Contrast

2000:1 full on/off

2000:1 full on/off

Black Level

2,0000 min. Lumen

0,89 min. Lumen

Lens shift

Vert.: +/-60% Hori.: +/-22% motorisiert

Resolution

HDTV 1920 x 1080
2.073.600 Pixel

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Wide screen width or rooms with plenty of light (over 200 lumens).

Light Source

1000W Xenon Lamp
Articel Nr.: 150-0126-00

Light Life

1000 h.

Operating Costs

-

Focus

Powered

Zoom

Powered

Objective

optional

Throw Ratio

optional

Audio

No

Connections

DVI mit HDCP in
5 x BNC RGBHV in
S-Video in
Cinch Video in
RS232C in und out
12V Trigger
weitere optional

Ceiling Mounting

Yes

Power

1650W

Size WxHxD

740 x 311 x 718 mm (29,1"x12,2"x28,3") 165,24 L/dm³

Operating Noise

-

Weight


54,43 kg / 120 lbs.

Keystone

-

Illumination

-



Frequenz H-sync: 15-120 kHz
V-sync: 23,97-150 Hz

Foot-Lamberts 165 fL / max. 643 cm screen width

565 cd/m²

- Features
- Full HD 1080P compatible
 - Lens shift Funktion motorisiert
 - Gamma correction
 - Picture-in-Picture
 - Remote control with backlight
 - Overscan adjustable
 - External video processor included.
- In Test -



| Optional Lenses | | | | | |
|----------------------|-------------|------------|---------|---------|---------|
| Name | Ratio | Distance | Shift V | Shift H | Zoom |
| Zoom Optional Lenses | | | | | |
| Runco Telesto E | 4.18-6.6:1 | 8.4-13.2 m | +/-60% | +/-22% | Powered |
| Runco Telesto D | 2.38-4:1 | 4.8-8 m | +/-60% | +/-20% | Powered |
| Runco Telesto C | 1.69-2.27:1 | 3.4-4.5 m | +/-60% | +/-22% | Powered |
| Runco Telesto B | 1.37-1.64:1 | 2.7-3.3 m | +/-60% | +/-22% | Powered |

Status 2006 Discontinued (EOL) // Last update of the data: 2023-08-04

Data

More Details



HCinema

<https://www.projector-database.com/pro/runcovx44d-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.