

Sanyo PLC XD2200

SANYO PLC XD2200



A brief introduction to the Sanyo PLC XD2200. The LCD projector has an XGA 1024 x 768 resolution and a contrast of 500:1. The lamp life is specified by the manufacturer as 4000 hours, which converts to over 5.5 years at 2 hours per day. Due to the brightness of 2200 Ansi lumens, a picture width of 408 cm is possible. In room light, the picture should be max. 272 cm wide. The model was built by Sanyo in 2010 and is no longer current.

 3 x 0,55" LCD TFT Panel mit MLA
XGA 4/3 Liquid Crystal Display with Micro Lense Array

Projector	2200 / 1540 im Eco Mode	733 Lux (bei 200 cm Screen)
Contrast	500:1 full on/off	500:1 full on/off
Black Level Offset	4,4000 min. Lumen	1,475 min. Lumen

XGA 1024 x 768

786.432 Pixel

UXGA 1600 x 1200 compressed

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Standard-Portabel | External training and company presentations, as well as product presentations.

Medium screen width or rooms with little light, max. 100 lumens.

215W UHP Lamp

Articel Nr.: 610 349 7518

4000 h. 6000 h. in Eco Mode

-

Manual


Manual 1,2

F=2,0-2,15 f=18,38-22,06 mm

1,62-1,92:1

1W Mono

D-sub 15 pin in
S-video in
Cinch Video in
Cinch Stereo in
RS232C Din 9 pin
RJ45 in





Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes
/ 186W in Eco Mode
333,5 x 94,2 x 247,0 mm (13,1"x3,7"x9,7") 7,73 L/dm³
34 / 29 dB in Eco Mode

Weight
Keystone
Illumination

2,50 kg / 5,51 lbs.
Vert.: +/-30° automatisch
85%

Frequenz

H-sync: 15-100 kHz
V-sync: 50-100 Hz
Range max.: 140 MHz

Foot-Lamberts

68 fL / max. 408 cm screen width
233 cd/m²

Features

- Direkt Power Off
- Freeze
- Blackboard Modus
- User logo
- Eco Mode
- Automatic and manual vertical keystone correction
- Kensington Slot
- Gamma correction
- Password protection
- PJLink™
- Lan network compatible.

Optional

Osram bulb only	NLMP19716
Lamp ruby	Ruby-LMP19716
Lamp original	610-349-7518 / LMP142 / ET-SLMP142
Compatible lamp	LMP-K19716
Remote control original	6451010766 / MXAT / CXZR
Air filter front original	610 345 0223
Air filter back original	610 346 5906
Ceiling Mount 100-120	Halterung100

Status

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n19716>
2010 Discontinued (EOL) // Last update of the data: 2023-08-04

Data



More Details



HCinema

<https://www.projector-database.com/pro/sanyoplcd2200-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.