

# Sanyo PLV HD2000N / E

SANYO PLV HD2000N / E



A brief introduction to the PLV HD2000N / E: The Sanyo stationary LCD projector offers 7000 Ansi lumens, a contrast of 1000:1 and HD2K 2048 x 1080 resolution. The projector also offers a lens shift function that makes image adjustment childs play. Thanks to the brightness of 7000 Ansi lumens, a picture width of 729 cm is possible. The projector can also handle slightly brighter rooms with a narrower picture width (we recommend max. 486 cm). Furthermore, the projector can play 1080P without any problems. The model was built by Sanyo in 2006 and is no longer current.

## Brief Introduction

Beta 2.5

## Display Type



3 x 1,65" LCD TFT Panel  
HD2K 4/3 Liquid Crystal Display

## Ansi-Lumen

Projector 7000

Screen 2333 Lux (bei 200 cm Screen)

## Contrast

1000:1

Screen 1000:1

## Black Level

7,0000 min. Lumen

Screen 2,34 min. Lumen

## Lens shift

Vert.: +/-50% Hori.: +/-10% motorisch

## Resolution

HD2K 2048 x 1080

## Video Modes

2.211.840 Pixel

UXGA 1600 x 1200 compressed

## Application

PAL, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

## Light Source

Very large screen width and rooms with plenty of light and shaded daylight.

## Light Life

4 x 300W UHP Lamp

Articel Nr.: 610-327-4928 / LMP100

## Operating Costs

-

## Focus

Powered

## Zoom

Powered

## Objective

optional

## Throw Ratio

optional

## Audio

3W Stereo

## Connections

DVI-I mit HDCP in

Dual link SDI

D-sub 15pin in

5 x BNC RGBHV in


Cinch Stereo in

RS232C

Weitere Anschlüsse optional.

## Ceiling Mounting

Yes



Power 1500W  
Size WxHxD 581 x 252 x 783 mm (22,9"x9,9"x30,8") 114,64 L/dm³  
Operating Noise -

Weight 37,50 kg / 82,67 lbs.  
Keystone -  
Illumination 90%

Frequenz H-sync: 15-120 kHz  
V-sync: 48-120 Hz  
Range max.: 230 MHz  
Foot-Lamberts 217 fL / max. 729 cm screen width  
743 cd/m²

- Full HD 1080P compatible
- Lens shift Funktion motorisch
- Freeze
- Eco Mode
- Gamma correction
- Optional LAN network compatible.

Features

Optional

Bulb only NLMP4903


Single lamp ruby Ruby-LMP4903

Single lamp original 610-327-4928 / LMP100 / ET-SLMP100

Compatible lamp LMP-K16051

Universal Remote original Fernb-uni-V3

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n4903>



Optional Lenses

| Name                 | Ratio       | Distance    | Shift V  | Shift H | Zoom    |
|----------------------|-------------|-------------|----------|---------|---------|
| Zoom Optional Lenses |             |             |          |         |         |
| Sanyo LNS-W06        | 1.1-1.5:1   | 2.2-3 m     | +/-39%   | +/-10%  | Powered |
| Sanyo LNS-W04        | 1.56-2.05:1 | 3.1-4.1 m   | +/-39%   | +/-10%  | Powered |
| Sanyo LNS-W02Z       | 1.4-1.83:1  | 2.8-3.7 m   | +/-39%   | +/-10%  | Powered |
| Sanyo LNS-T03        | 6.23-9.7:1  | 12.5-19.4 m | +/-50%   | +/-10%  | Powered |
| Sanyo LNS-T02        | 4.4-6.13:1  | 8.8-12.3 m  | +/-50%   | +/-10%  | Powered |
| Sanyo LNS-S03        | 2.6-3.52:1  | 5.2-7 m     | +/-50%   | +/-10%  | Powered |
| Sanyo LNS-S02Z       | 2.01-2.63:1 | 4-5.3 m     | +/-66.7% | +/-10%  | Powered |
| Sanyo LNS-M01Z       | 3.44-4.45:1 | 6.9-8.9 m   | +/-50%   | +/-10%  | Powered |

Fix Optional Lenses

|                |       |        |          |        |         |
|----------------|-------|--------|----------|--------|---------|
| Sanyo LNS-W03  | 0.8:1 | 1.6 m  | 0.0% Fix |        | No Zoom |
| Sanyo LNS-T01Z | 6.9:1 | 13.8 m | +/-50%   | +/-10% | No Zoom |
| Sanyo LNS-W01Z | 1.2:1 | 2.4 m  | +/-39%   | +/-10% | No Zoom |

Status 2006 Discontinued (EOL) // Last update of the data: 2023-08-04

Data



More Details



HCinema

<https://www.projector-database.com/pro/sanyoplvd2000n-en.html>