

Videoseven PD480C

VIDEOS EVEN PD480C



Brief Introduction

Beta 2.5

Display Type

Ansi-Lumen

Contrast

Black Level

Offset

Resolution

Video Modes

Disc Recognition

Application

Light Source

Light Life

Operating Costs

Focus

Zoom

Objective

Throw Ratio

Audio

Connections

Ceiling Mounting

The Videoseven PD480C home cinema DLP projector has 1100 Ansi lumens, a contrast of 2000:1 and a WVGA 854 x 480 resolution. The projector can illuminate a picture width of up to 337 cm thanks to the 1100 Ansi lumens. In room light, however, the image width should ideally be less than 225 cm. The model was built by Videoseven in 2005 and is no longer current.



1 x 0,55" DDR DLP Chip
WVGA 16/9 Ti Digital Light Processing Chip

Projector
Screen

1100

2000:1 full on/off

0,5500 min. Lumen

489 Lux (bei 200 cm Screen)

2000:1 full on/off

0,245 min. Lumen

WVGA 854 x 480

409.920 Pixel

SXGA 1280 x 1024 compressed

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

DVD | HD Blu-ray (komprimiert) | 3D Blu-ray | 4K UHD Blu-ray

Homecinema | Small screen width, rooms with very little ambient light below 100 lumens.

200W Osram Lamp

Articel Nr.: LMP15689

2000 h.

8,22% / 0,06 €

Manual

Manual 1,2

f=22-26,7 mm

1,83-2,19:1

1 x 2W


D-sub 15pin in

Cinch Video in


S-Video in

Mini Jack in

USB



Yes



Power 260W
Size WxHxD 254 x 98 x 202 mm (10"x3,9"x8") 5,03 L/dm³
Operating Noise 34 / 32 dB in Eco Mode

Weight 2,20 kg / 4,85 lbs.
Keystone Vert.: +/-15°
Illumination 80%
H-sync: 31-79 kHz
Frequenz V-sync: 50-85 Hz
Range max.: 135 MHz
Foot-Lamberts 45 fL / max. 337 cm screen width
154 cd/m²
Features

- Blank (Black screen button)
- Eco Mode
- Gamma correction
- De-interlacer with 3:2 pull down

Optional Bulb only Osram NLMP15689
Lamp ruby Ruby-LMP15689
Lamp original LMP15689

Status Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n15689>
2005 Discontinued (EOL) // Last update of the data: 2023-08-04



More Details



<https://www.projector-database.com/pro/videosevenpd480c-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.