

Vidikron Vision Model 10

VIDIKRON VISION MODEL 10



A brief introduction to the Vidikron Vision Model 10. The DLP projector has a WPAL 1024 x 576 resolution and a contrast of 2400:1. The built-in lens shift and keystone correction function provides freedom when setting up. A picture width of up to 284 cm is possible. However, the picture should be smaller in room light. We recommend max. 189 cm. It is also Full HD 1080P compatible. The model was built by Vidikron in 2005 and is no longer current.

Brief Introduction

Beta 2.5

Display Type



1 x DLP Chip

WPAL 16/9 Ti Digital Light Processing Chip

Ansi-Lumen

Projector

780 / 410 Home Theater Calibration

Screen

347 Lux (bei 200 cm Screen)

Contrast

2400:1 full on/off

2400:1 full on/off

Black Level

0,3250 min. Lumen

0,145 min. Lumen

Lens shift

Vert.: +/-50% Hori.: +/-10%

Resolution

WPAL 1024 x 576

489.824 Pixel

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Disc Recognition

DVD | HD Blu-ray (komprimiert) | 3D Blu-ray | 4K UHD Blu-ray

Application

Homecinema | Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

250W NSH Lamp

Light Life

2000 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,14

Objective

-

Throw Ratio

1,4-1,6:1

Audio

-

Connections

DVI mit HDCP
D-sub 15pin in
S-Video
Cinch Video
RS232C

Ceiling Mounting

Yes

Power

370W

Size WxHxD


399,27 x 163,47 x 430,00 mm (15,7"x6,4"x16,9") 27,97 L/dm³

Operating Noise

-

Weight

-



Keystone Illumination	Vertical -
Frequenz	-
Foot-Lamberts	32 fL / max. 284 cm screen width 110 cd/m ²
Features	■ Full HD 1080P compatible ■ Lens shift Funktion ■ Gamma correction ■ Overscan adjustable
Status	2005 Discontinued (EOL) // Last update of the data: 2023-08-04



More Details

HCinema

<https://www.projector-database.com/pro/vidikronvision10-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.